

American Nuclear Society


containment system leakage
testing requirements

WITHDRAWN

November 27, 2002
ANSI/ANS-56.8-1994

an American National Standard

No longer being maintained as an American National Standard. This standard may contain outdated material or may have been superseded by another standard. Please contact the ANS Standards Administrator for details.



published by the
American Nuclear Society
555 North Kensington Avenue
La Grange Park, Illinois 60525 USA

ANSI/ANS-56.8-1994

**American National Standard
for Containment System Leakage
Testing Requirements**

Secretariat
American Nuclear Society

Prepared by the
**American Nuclear Society
Standards Committee
Working Group ANS-56.8**

Published by the
**American Nuclear Society
555 North Kensington Avenue
La Grange Park, Illinois 60525 USA**

Approved August 4, 1994
by the
American National Standards Institute, Inc.

American National Standard

Designation of this document as an American National Standard attests that the principles of openness and due process have been followed in the approval procedure, and that a consensus of those directly and materially affected by the standard has been achieved.

This standard was developed under the procedures of the Standards Committee of the American Nuclear Society. These procedures are accredited by the American National Standards Institute, Inc., as meeting the criteria for American National Standards. The consensus committee that approved the standard was balanced to ensure that competent, concerned, and varied interests have had an opportunity to participate.

An American National Standard is intended to aid industry, consumers, governmental agencies, and general interest groups. Its use is entirely voluntary. The existence of an American National Standard, in and of itself, does not preclude anyone from manufacturing, marketing, purchasing, or using products, processes, or procedures not conforming to the standard.

By publication of this standard, the American Nuclear Society does not insure anyone utilizing the standard against liability allegedly arising from or after its use. The content of this standard reflects acceptable practice at the time of its approval and publication. Changes, if any, occurring through developments in the state of the art, may be considered at the time that the standard is subjected to periodic review. It may be reaffirmed, revised, or withdrawn at any time in accordance with established procedures. Users of this standard are cautioned to determine the validity of copies in their possession and to establish that they are of the latest issue.

The American Nuclear Society accepts no responsibility for interpretations of this standard made by any individual or by any ad hoc group of individuals. Requests for interpretation should be sent to the Standards Department at Society Headquarters. Action will be taken to provide appropriate response in accordance with established procedures that ensure consensus on the interpretation.

Comments on this standard are encouraged and should be sent to Society Headquarters.

Published by

American Nuclear Society
555 North Kensington Avenue, La Grange Park, Illinois 60525 USA

Copyright © 1994 by American Nuclear Society.

Any part of this standard may be quoted. Credit lines should read "Extracted from American National Standard ANSI/ANS-56.8-1994 with permission of the publisher, the American Nuclear Society." Reproduction prohibited under copyright convention, unless written permission is granted by the American Nuclear Society.

Printed in the United States of America

Foreword

(This foreword is not part of American National Standard for Containment System Leakage Testing Requirements, ANSI/ANS-56.8-1994.)

This standard provides a basis for determining leakage rates through the primary reactor containment systems of light-water-cooled nuclear power plants.

The leakage rate tests performed on the primary reactor containment system simulate some of the conditions (e.g., penetrations vented, flooded, or in operation) that exist during a design basis accident. The test methodology and the associated requirements for both whole containment (integrated) and individual pathway (local) leakage rate testing are contained in this document.

The appendices contain Type A and verification test methods, formula derivations, data rejection criteria, containment atmosphere stabilization criteria, and test termination criteria.

The regulatory requirements for containment leakage rate testing are contained in Title 10, "Energy," Code of Federal Regulations (CFR), Part 50, "Domestic Licensing of Production and Utilization Facilities," Appendix J, "Leakage Rate Testing of Containments of Light-Water-Cooled Nuclear Power Plants." This standard is not in complete agreement with the current version of Appendix J.

The previous revision to this standard was issued in 1987. This revision was written to take advantage of subsequent advancements in computer and instrument technology. Also incorporated are items which the committee believed to be improvements in testing methodology and requirements. These include: an as-found and as-left section, minimum and maximum pathway leakage rates, test termination limits, containment air mass stabilization criteria, and improved data rejection guidelines.

Working Group ANS-56.8 of the Standards Committee of the American Nuclear Society had the following membership at the time it approved this standard:

J. Glover, Chairman, <i>Commonwealth Edison Company</i>	P. Nielsen, <i>Pacific Gas & Electric Company</i>
T. Renton, Secretary, <i>TER Services, Inc.</i>	B. Patel, <i>Bechtel Power Corporation</i>
J. Carp, <i>Volumetrics, Inc.</i>	D. Peyvan, <i>DHP Consulting Services</i>
K. Hartranft, <i>Ebasco Services, Inc.</i>	J. Pulsipher, <i>US Nuclear Regulatory Commission</i>
H. Hill, <i>BCP Technical Services, Inc.</i>	M. Schreiber, <i>Toledo Edison Company</i>
M. Hutcheson, <i>Duke Power Company</i>	C. Serata, <i>Public Service Electric & Gas Company</i>
M. Jennex, <i>Southern California Edison Company</i>	R. Shirk, <i>General Physics Corporation</i>
D. Lurie, <i>US Nuclear Regulatory Commission</i>	E. Tarnuzzer, Chairman Emeritus, <i>Yankee Atomic Electric Company</i>
M. Marugg, <i>American Nuclear Insurers</i>	J. Zimmerman, <i>United Energy Services Corporation</i>
S. Morales, <i>Omaha Public Power District</i>	
K. Mulling, <i>Entergy</i>	

The American Nuclear Society's Nuclear Power Plant Standards Committee (NUPPSCO) had the following membership at the time of its ballot for approval of this standard:

W. H. D'Ardenne, Chairman

M. D. Weber, Secretary

R. E. Allen	UE&C Nuclear
P. Ballinger	Nebraska Public Power District
S. Bhattacharya	Pacific Gas & Electric Company
F. Boorboor	Nuclear Placement Services, Inc.
J. C. Bradford	Bechtel National, Inc.
T. W. Burnett	Westinghouse Electric Corporation
J. D. Cohen	Savannah River Laboratory
J. D. Cotton	Philadelphia Electric Company
T. A. Daniels	Rochester Gas & Electric Corporation
W. H. D'Ardenne	GE Nuclear Energy
L. E. Davis	Commonwealth Edison Company
S. B. Gerges	NUS Corporation, Inc.
D. L. Gillispie	Institute of Nuclear Power Operations
G. L. Gyorey	GE Nuclear Energy
P. H. Hepner	ABB/Combustion Engineering Nuclear Power
C. E. Johnson, Jr.	U.S. Nuclear Regulatory Commission
J. T. Luke	Florida Power & Light Company
J. F. Mallay	Liberty Consulting Group
R. E. Miller	Duke Power Company
J. A. Nevshemal	UE&C/Stearns Rogers
W. B. Reuland	Electric Power Research Institute
T. T. Robin	Southern Company Services, Inc.
J. C. Saldarini	Ebasco Services, Inc.
R. E. Scott	Scott Enterprises
D. J. Spellman	Oak Ridge National Laboratories
S. L. Stamm	Stone & Webster Engineering Corporation
J. D. Stevenson	Stevenson & Associates
C. D. Thomas, Jr.	Yankee Atomic Electric Company
G. P. Wagner	Commonwealth Edison Company
N. Weber	Sargent & Lundy
R. Weir	Tennessee Valley Authority

Contents	Section	Page
	1. Introduction	1
	1.1 Purpose	1
	1.2 Scope	1
	2. Definitions	1
	3. Leakage Testing Requirements	4
	3.1 General	4
	3.2 Type A Test Requirements	4
	3.3 Local Leakage Rate Testing Requirements	6
	3.4 Qualified Seal System Testing Requirements	7
	4. Instrumentation	7
	4.1 Calibration	7
	4.2 Pretest Checks (Type A Test)	7
	4.3 Instrumentation Specifications	8
	4.4 Sensor Rejection Criteria	9
	5. CILRT Procedure	9
	5.1 Recording of Data	9
	5.2 Containment Drybulb Temperature Survey	9
	5.3 Pressurization	10
	5.4 Preoperational Test Pressure	10
	5.5 Computation of Type A Leakage Rate	10
	5.6 Containment Atmosphere Stabilization	11
	5.7 Termination Limits	11
	5.8 Type A Test Acceptance Criteria	11
	5.9 Verification Test	12
	5.10 Depressurization	12
	5.11 Reporting of Results	12
	5.12 Containment Leakage Rate Backup Data	13
	6. Test Procedures for Type B and Type C Tests	13
	6.1 General Methods	13
	6.2 Direction of Testing	13
	6.3 System Line-Up	13
	6.4 Test Methods	13
	7. References	14
 Appendices		
	Appendix A Type A Test Methods	16
	Appendix B Bases and Formulae for Containment Type A Tests	17
	Appendix C Verification Test Method	21
	Appendix D Data Rejection Criteria	22
	Appendix E Containment Atmosphere Stabilization Criteria	27
	Appendix F Vapor Pressure and Volume Change Calculations	29
	Appendix G Termination Limit Criteria	31

Section	Page
Figure	
Figure 6-1 Typical Minimum and Maximum Pathway Determinations . . .	15
Tables	
Table B1 95th Percentile of the Student's t Distribution for Selected Degrees of Freedom	20
Table D1 Sample Containment Air Mass and Calculations for Detection of a Single Outlier	24
Table D2 Critical Deviation Ratio for Data Rejection for a One-Sided Statistical Test	25
Table E1 Sample Problem	28
Table G1 Sample Problem	34

Containment System Leakage Testing Requirements

1. Introduction

1.1 Purpose. This standard provides a basis for determining leakage rates through the primary containment of light-water reactor nuclear power plants.

The examples given in various sections of this standard do not contain or modify any requirements. These examples are for illustration only and clarify the intent of the text. Furthermore, the examples are not meant to be all-inclusive. Examples of alternative methods or exceptions to general requirements do not constitute permission to categorically apply the exceptions. Each alternative or exception needs to be evaluated to determine its validity and effect.

1.2 Scope.¹ This standard specifies acceptable primary containment leakage rate test requirements to assure valid testing. The scope includes

- (1) Leakage test requirements
- (2) Test instrumentation
- (3) Test procedures
- (4) Test methods
- (5) Acceptance criteria
- (6) Data analysis
- (7) Inspection and reporting of test results.

2. Definitions²

The following terms are for general use in this standard:

acceptance criteria. The standards against which test results are to be compared for establishing the functional acceptability of the primary containment as a leakage limiting boundary.

accuracy. Conformity of an indicated value to an accepted standard value or true value.

¹ At the time this standard was approved, it contained certain requirements (i.e., testing frequency requirements) that were not fully consistent with existing regulations in the United States. The user of the standard should ensure that its application in a regulated facility is appropriate.

² Specialized definitions used in the appendices are defined in the appendix where they are used.

active failure. A malfunction, excluding passive failures, of a component which relies on mechanical movement or change of state to complete its intended function upon demand. Examples of active failures include the failure of a valve or a check valve to move to its correct position, or the failure of a pump, fan, or diesel generator to start. Spurious action of a power-operated component originating within its actuation or control system shall be regarded as an active failure unless specific design features or operating restrictions preclude such spurious action. An example is the unintended energization of a power-operated valve to open or close.

as-found leakage rate. The leakage rate prior to any repairs or adjustments to the barrier being tested.

as-found testing. Leakage rate testing after some period of normal service conditions, performed prior to any repairs or adjustments.

as-left leakage rate. The leakage rate following any repairs or adjustments to the barrier being tested.

as-left testing. Leakage rate testing performed following repair or adjustment.

confidence level. The probability that the true leakage rate does not exceed the upper confidence limit.

containment atmosphere volume weighted average temperature (T). The temperature derived from weighting each temperature sensor reading by the volume it represents.

containment integrated leakage rate test (CILRT). The leakage rate test performed on the primary containment by simulating some of the conditions (e.g., penetrations vented, drained, flooded, or in operation) that exist during a design basis accident. The CILRT consists of the following phases or activities:

- (1) inspecting the primary containment
- (2) pressurizing the primary containment system
- (3) stabilizing the containment atmosphere